

Clarification #1

Subject: Provision of clarifications regarding Tender TED143 concerning the “Supply and installation of new equipment for the upgrade of Electrical Substation No. 7.5 of ThPA S.A.”

Question #1: In the technical description, a prefabricated substation building (kiosk) with dimensions of 3.5 m × 8 m and a specific partitioning layout is mentioned, whereas the drawings indicate different dimensions (2.8 m × 6.5 m and 3 m × 5.45 m) as well as a different partitioning layout. Kindly clarify which of the above applies, as well as the required final height of the kiosk.

ThPA S.A. Response #1: The bidders shall consider a prefabricated substation building with a floor plan of 3.5 m × 8 m and partitioning in accordance with the technical specifications described in Part B – Technical Specifications.

The panels of the low-voltage switchboards specified have a height of approximately 210 cm, to which an additional 10–20 cm should be added for the base. The total height of the kiosk shall be determined by the bidders’ design, taking into account the offered equipment as well as the required safety clearances in accordance with the applicable standards and relevant legislation for MV substations.